

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-03026-00-02
Spot: SESENE Sec/Twnshp/Rge: 5-10S-21W
2310 feet from N Section Line, 330 feet from E Section Line
Lease Name: RUDMAN Well #: 2
County: GRAHAM Total Vertical Depth: 2453 feet

Operator License No.: 34746
Op Name: SPIRAL ENERGY CORP
Address: 300 N MARIENFELD
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3938		
SURF	8.625	185		175 SX

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 09/09/2013 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BERENS Company: SPIRAL ENERGY CORP Phone: (785) 688-4040

Proposed Lost Hole
Plugging Washed well down to 2452' (hard steel). Unable to get below 2452'.
Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/200 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/09/2013 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Perfs:

Ran tubing to 2450'. Allied pumped 100 sx cement w/100 # hulls.
Pulled tubing to 1225'. Allied pumped 135 sx cement w/100 # hulls.
Cement circulated. PTOH. Topped 5 1/2" casing off w/25 sx cement. Casing full.
GPS: 39.21331 -099.68085

Remarks: ALLIED CEMENTING

Plugged through: TBG

KCC WICHITA
SEP 17 2013
RECEIVED

District: 04

Signed

Richard Williams
11/18/13 (TECHNICIAN)

CM

SEP 12 2013