

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03250-00-00
Spot: SENWSE Sec/Twnshp/Rge: 22-15S-18W
1650 feet from S Section Line, 1650 feet from E Section Line
Lease Name: PIVONKA B Well #: 1
County: ELLIS Total Vertical Depth: 3609 feet

Operator License No.: 33585

Op Name: STECKLEIN OIL COMPANY, A GENERAL PARTNERSHIP

Address: 1312 GOLDEN BELT DR
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3575		
PROD	5.5	3609		75 SX
ARF	9	852		200 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 09/23/2013 8:00 AM

Plug Co. License No.: 34717

Plug Co. Name: STECKLEIN, DAN DBA AVID WELL SERVICE

Proposal Rcvd. from: DAN STECKLEIN

Company: STECKLEIN OIL CO.

Phone: (785) 650-7706

Proposed Plugging Method: Ordered 600 sx 60/40 pozmix 4% gel cement w/800 # hulls.
Emergency plug with rig over hole.
Casing leaks
Tubing in hole at 2500'.
Perforations - ARB - 3592'. CIBP at 3575. Perforations - LKC - 3496' - 3504', 3478 - 3482'.
GPS: 38.73054 -099.30705
1689' FSL 1624' FEL
NE SE NW SE

Plugging Proposal Received By: PAT STAAB

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 09/23/2013 3:15 PM

KCC Agent: PAT STAAB

Actual Plugging Report:

L.K. Wire line perforated at 1650', 1207' and 800'.
Stecklein ran in hole with tubing to 2425'. Quality rigged to tubing and mixed and pumped 120 sx cement with 300 # hulls mixed in.
Pulled tubing to 1200' and pumped 40 sx cement w/100 # hulls mixed in.
Pulled tubing to 800' and pumped 240 sx cement w/200 # hulls. Ran out of cement only.
Brought 400 sx cement and ordered 200 sx cement more.
Rigged to tubing and pumped 85 sx cement w/300 # hulls to circulate cement up 9" casing and 5 1/2" casing. Pulled tubing. Shut in 9" casing. Rigged to 5 1/2" casing with a swedge and pumped 25 sx cement to pressure with 300 psi and 300 psi shut in pressure.

Perfs:

Top	Bot	Thru	Comments
3496	3504		
3478	3482		

Remarks: QUALITY CEMENTING CO TICKET # 7772

Plugged through: TBG

District: 04

Signed

[Signature]
9/18/13

RECEIVED
KANSAS CORPORATION COMMISSION

CM

SEP 25 2013

OCT 02 2013

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS