

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-207-22309-00-02

Spot: SESESE

Sec/Twnshp/Rge: 6-24S-17E

220 feet from S Section Line, 220 feet from E Section Line

Lease Name: WOOD

Well #: 1

County: WOODSON

Total Vertical Depth: 1220 feet

Operator License No.: 30345

Op Name: PIQUA PETRO, INC.

Address: 1331 XYLAN RD  
PIQUA, KS 66761

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1190		
SURF	7	64		

Well Type: EOR

UIC Docket No: E29033.2

Date/Time to Plug: 05/29/2012 12:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: Run 1" pipe to TD. Circulate cement from TD to surface.

Plugging Proposal Received By: RYAN DULING

WitnessType: NONE

Date/Time Plugging Completed: 05/29/2012 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Washed down the inside of the 2.875" casing to TD with 1" pipe. Pumped 36 sacks of portland cement through the 1" pipe at TD. Pulled 1" pipe to 600'. Circulated cement from 600' to surface. Pulled 1" pipe to 200'. Circulated cement from 200' to surface. Pulled the rest of the 1" pipe. Topped well off with cement. A total of 48 sacks of portland cement was reported used to plug this well.

RECEIVED

OCT 29 2013

KCC Chanute Dist. #3

RD

Remarks:

Plugged through: TBG

District: 03

Signed

cc to MIC 11/06/13 (TECHNICIAN)

11/15/13

KCC WICHITA

Form CP-2/3

OCT 31 2013

RECEIVED