

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-039-20570-00-00
Spot: SESENW Sec/Twnshp/Rge: 1-1S-26W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease Name: JOLLY Well #: 6-1
County: DECATUR Total Vertical Depth: 3637 feet

Operator License No.: 33595
Op Name: PLATTE VALLEY OIL CO., INC.
Address: 7551 MAIN ST STE 253 PO BOX 27012
RALSTON, NE 68127

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3637		150 SX
SURF	8.625	206		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/11/2013 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILL KENTOPP Company: PONCHO Phone: (308) 340-5026

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement w/650 # hulls.
Perforations: 1985', 1335' and 195'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 09/11/2013 2:30 PM KCC Agent: TOM CULLEY

Actual Plugging Report:

2 3/8" tubing stacked out at 3416'. Perforated casing at 1985', 1335' and 195'. Ran tubing to 3416' and pumped 80 sx cement w/300 # hulls. Pulled tubing to 2250' and pumped 75 sx cement w/200 # hulls.
Pulled tubing to 1125' and pumped 60 sx cement w/150 # hulls. Cycled cement from 4 1/2" casing. Topped off 8 5/8" x 4 1/2" annulus with 50 sx cement. Pumped 10 sx to top off well bore.

GPS: 39.99522 -100.18858

Perfs:

Top	Bot	Thru	Comments
3432	3435		
3422	3424		
3351	3357		

Remarks: SWIFT SERVICES TICKET # 24935

Plugged through: TBG

District: 04

Signed _____

[Signature]
11/16/13 (TECHNICIAN) *CM*

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

SEP 17 2013

OCT 02 2013

CONSERVATION DIVISION
WICHITA, KS