

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-04374-00-00
Spot: SWNESW Sec/Twnshp/Rge: 27-19S-9W
1693 feet from S Section Line, 3656 feet from E Section Line
Lease Name: SLEDD Well #: 1
County: RICE Total Vertical Depth: 3227 feet

Operator License No.: 32846
Op Name: PREMIER OIL & EXPLORATION INC
Address: 1100 AIRPORT RD
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3219		0 SX
SURF	8.625	210		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/21/2013 12:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMMIE HARRIS Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-0895

Proposed Plugging Method: PER KCC RULES. CONDITION OF WELL IS POOR, AS INDICATED ON CPI. 4.5" LINER HAS BEEN SET AT UNKNOWN DEPTH.

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/15/2013 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. AND OH TO 3150' AND CAP WITH 5 SX'S CEMENT. PERFRATE AT 1150', 750', AND 260'. RUN TUBING TO 1150' AND PUMP 35 SX'S COMMON CEMENT. PULL TUBING TO 750' AND PUMP 35 SX'S COMMON CEMENT, PULL TUBING TO 260' AND CIRCUALTE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF . CEMENT CIRCULATED UP ALL CASING.

Perfs:

Top	Bot	Thru	Comments
3219	3227	OH	

Remarks: COPELAND TICKET #41905. LOG TECH OF KS #7649

Plugged through: TBG

District: 02

Signed

Virgil Clothier
10/15/13

(TECHNICIAN)

KCC WICHITA

NOV 04 2013

Form CP-2/3

RECEIVED

JK