

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20902-00-01  
Spot: SWSW Sec/Twnshp/Rge: 10-33S-31W  
696 feet from S Section Line, 4568 feet from E Section Line  
Lease Name: ORMISTON Well #: 2  
County: SEWARD Total Vertical Depth: 6050 feet

Operator License No.: 4058  
Op Name: AMERICAN WARRIOR, INC.  
Address: 3118 CUMMINGS RD PO BOX 399  
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5000		WITH 2 SX CMT
PROD	5.5	6049	2705	WITH 200 SX CMT
SURF	8.625	1594		WITH 610 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2013 8:30 AM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5550' & 2 SX CMT. PLUG AT 1620' WITH 50 SX CMT. PLUG AT 530' WITH 40 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2013 1:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 5000' WITH 2 SX CMT. 1ST PLUG AT 1620'. LOADED HOLE WITH GEL THEN PUMP 50 SX CMT. 2ND PLUG AT 530' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT. HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
5604	5619		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Eric MacLaren  
10/23/13 (TECHNICIAN)

RECEIVED  
OCT 29 2013  
KCC DODGE CITY

KCC WICHITA Form CP-2/3

NOV 01 2013

RECEIVED