

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21943-00-00
Spot: NESWSE Sec/Twnshp/Rge: 2-13S-16W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WINDHOLZ Well #: 1
County: ELLIS Total Vertical Depth: 3443 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3441		125 SX
SURF	8.625	173		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/09/2013 12:30 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: JOE SMITH Company: AMERICAN WARRIOR INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: LCK 3182' - 3427'.
Express Well Service milled on well 4 days and got to 1135'. May be outside casing.
GPS: 38.94653 -099.06404
1007' FSL 1729' FEL
NW NE SW SE

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/09/2013 5:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Pioneer perforated at 613'. Could not get down hole to 1107'. Perf spot with gun. Casing hole was caving in. Ran in hole with tubing to 1113'. Swift rigged to tubing and pumped 175 sx cement w/450 # hulls to circulate cement to surface. Pulled tubing. Topped off 4 1/2" casing with 65 sx cement. Hole standing full. Rigged to 8 5/8" casing and pumped 60 sx cement to pressure with 200 psi. Shut in pressure 200 psi.

Perfs:

Top	Bot	Thru	Comments
3182	3427		

Remarks: SWIFT CEMENTING SERVICES TICKET # 25211

Plugged through: TBG

District: 04

Signed


10/14/13 (TECHNICIAN)

CM

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

OCT 10 2013

OCT 21 2013
CONSERVATION DIVISION
WICHITA, KS