

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-22844-00-01
Spot: NWNWNESE Sec/Twnshp/Rge: 3-25S-5E
2395 feet from S Section Line, 993 feet from E Section Line
Lease Name: CAMERON A Well #: 7
County: BUTLER Total Vertical Depth: 2710 feet

Operator License No.: 33907
Op Name: MAX OIL LLC
Address: 746 WESTCHESTER
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	2628		
PKR		2601		
PROD	5.5	2563		50 SX
SURF	8.625	218		110 SX
T1	2.375	2601		

Well Type: SWD UIC Docket No: D28176.0 Date/Time to Plug: 08/29/2013 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: TERRY SATTERFIELD Company: MAX OIL Phone: (316) 733-9663

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/29/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

MILLED TBG @ 868'. RIH W/PACKER & TBG SET @ 830', CONSOLIDATED MIXED & SQUEEZED 100 SXS CLASS A COMMON 3% CC. WAITED 2 HRS. LAYED DOWN TBG. LOADED HOLE & PRESSURED CASING. HELD OK. RIH ON WIRELINE. SHOT SQUEEZE HOLES 270'-271' (2 HOLES). SWEDGED INTO 4 1/2" CASING, ESTABLISHED CIRCULATION, MIXED & PUMPED 115 SXS 60/40 POZMIX 2% GEL 3% CC TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-29-2013. CONSOLIDATED OIL WELL TICKET # 43883.

Perfs:

Top	Bot	Thru	Comments
2628	2710	OH	

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 06 2013
CONSERVATION DIVISION
WICHITA, KS

RECEIVED
KANSAS CORPORATION COMMISSION
SEP 05 2013

Remarks: FAILED MIT/LEFT TBG & PACKER PARTED IN HOLE, (868'-2601')

Plugged through: TBG

District: 02

Signed DUANE KRUEGER
(TECHNICIAN)
cc to UIC 9/06/13
IK