

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-069-20439-00-00  
Spot: NESWNW Sec/Twnshp/Rge: 33-29S-30W  
1650 feet from N Section Line, 990 feet from W Section Line  
Lease Name: LOUK TRUST "A" Well #: 1-33  
County: GRAY Total Vertical Depth: 5650 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1819		WITH 600 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/13/2013 8:00 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: UVALDO MARTINEZ Company: STERLING DRILLING COMPANY Phone: (620) 672-9508

Proposed Plugging Method: 1ST PLUG AT 1850' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSEHOLE WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE  
Date/Time Plugging Completed: 09/13/2013 8:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

COMPANY RAN A BASKET ON 8 5/8" AT 120'. CMT DID NOT CIRCULATE ON 8 5/8" ON INITIAL CMT JOB. RAN 1" TO 70' & PUMPED 150 SX CMT. RAN BOND LOG TO DETERMINE CMT TOP. HAD GOOD CMT 0'-640', FAIR CMT 640' TO 800', INTERMITTENT CMT 800' TO 1819'. 1ST PLUG AT 1850' WITH 50 SX CMT. 2ND PLUG AT 800' WITH 40 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

Signed

Richard W. Lacey  
09/23/13 (TECHNICIAN)  
KCC WICHITA

RECEIVED  
SEP 19 2013  
KCC DODGE CITY

SEP 23 2013  
RECEIVED