

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-077-21038-00-00
Spot: NWNENW Sec/Twnshp/Rge: 11-34S-8W
4950 feet from S Section Line, 3630 feet from E Section Line
Lease Name: RITTER E Well #: 1-11
County: HARPER Total Vertical Depth: 4750 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4748		150 SX
SURF	8.625	255		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/03/2013 4:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADY Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 10/03/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

10/2/13 - SET CIBP @ 4500' CAPPED WITH 2 SX CEMENT. TRIED TO CUT CASING, FAILED AFTER NUMEROUS TRIES, CUT HEAD APART SO COULD OBSERVE BACKSIDE. 10/3/13 --USED WIRELINE TRUCK TO PERF - WITH 4 SHOTS @ 1350' @ 900' AND 300'. RAN TUBING INTO 1350' SPOTTED 35 SX CEMENT, PULLED TUBING TO 900' SPOTTED 35 SX CEMENT, PULLED TUBING TO 300' CIRCULATED TO SURFACE WITH 165 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4674	4698		

Remarks: QUALITY WELL SERVICE ALSO SUPPLIED THE CEMENT, AND PUMP TRUCK.

Plugged through:

District: 02

Signed

BJ Hope
10/24/13

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2013 rm CP-2/3

CONSERVATION DIVISION
WICHITA, KS

1/34