

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20415-00-00
Spot: NESWNWSE Sec/Twnshp/Rge: 4-26S-13W
1764 feet from S Section Line, 2223 feet from E Section Line
Lease Name: BELDEN-CHANCE Well #: 1
County: PRATT Total Vertical Depth: 4265 feet

Operator License No.: 30116
Op Name: JONES OIL, LLC
Address: 112 N GRAY
ST JOHN, KS 67576

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3725 | | WITH 2 SX CMT |
| CIBP | | 3980 | | |
| CIBP | | 4125 | | |
| PROD | 4.5 | 4264 | 2020 | WITH 225 SX CMT |
| SURF | 8.625 | 327 | | WITH 275 SX CMT |

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/27/2013 9:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JEFF BURKE Company: PETERRA ENERGY SERVICES Phone: (316) 269-2015

Proposed Plugging Method: SET CIBP @ 3725' & 2 SX CMT. PLUG AT 850' WITH 20 SX GEL & 50 SX CMT. PLUG AT 360' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: KEN JEHLIK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/27/2013 12:15 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3725' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 840' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 360' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4146 | 4187 | | |
| 3994 | 3998 | | |
| 3908 | 3912 | | |
| 3893 | 3897 | | |
| 3760 | 3766 | | |

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 15 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

OCT - 4 2013

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)