

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23897-00-00  
Spot: SENWNENE Sec/Twnshp/Rge: 28-11S-14W  
472 feet from N Section Line, 814 feet from E Section Line  
Lease Name: BAR S RANCH 28 Well #: 1  
County: RUSSELL Total Vertical Depth: 3518 feet

Operator License No.: 34158  
Op Name: O'BRIEN RESOURCES, LLC  
Address: PO BOX 6149  
SHREVEPORT, LA 71136

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	262		180 SX

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2013 12:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: SCOTT EDWARDS Company: ALLIED CEMENT COMPANY Phone: (620) 639-4014

Proposed Plugging Method: Ordered 230 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: EDWIN SCHUMACHER WitnessType: NONE  
Date/Time Plugging Completed: 08/13/2013 4:45 PM KCC Agent: EDWIN SCHUMACHER

Actual Plugging Report:

1st plug @3498 w/50 sx  
2nd plug @850 w/25 sx  
3rd plug @460 w/100 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: ALLIED  
Plugged through: DP

KCC WICHITA  
SEP 17 2013  
RECEIVED

District: 04

Signed Ed Schumacher  
11/08/13 (TECHNICIAN) CM

SEP 12 2013