

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-023-20045-00-00
Spot: SE Sec/Twnshp/Rge: 5-3S-41W
1320 feet from S Section Line, 1320 feet from E Section Line
Lease Name: ALVIN ZWEYGARDT Well #: 1
County: CHEYENNE Total Vertical Depth: 1613 feet

Operator License No.: 33019
Op Name: ROSEWOOD RESOURCES, INC.
Address: 2101 CEDAR SPRINGS RD, STE 1500
DALLAS, TX 75201

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1606		100 SX
SURF	8.625	251		220 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/24/2013 2:00 PM
Plug Co. License No.: 33532 Plug Co. Name: ADVANCED DRILLING TECHNOLOGIES LLC
Proposal Rcvd. from: TOM ROELFS Company: ROSEWOOD Phone: (970) 324-1686

Proposed Plugging Method: Ordered 200 sx common cement and 50 # hulls.
8 5/8" surface casing set at 251' w/220 sx cement. 4 1/2" production casing set at 1606' w/100 sx cement.
Perforations: 1430' - 1460', TD 1613'

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/24/2013 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Connected to 4 1/2" production casing. Pumped 120 sx cement w/50 # hulls. Maximum pressure 150 psi. Connected to 8 5/8" surface casing and pumped 30 sx cement. Maximum pressure 400 psi.
GPS: 39.81814 N -101.94181 W

Perfs:

Top	Bot	Thru	Comments
1430	1460		

Remarks: ADVANCED DRILLING TECHNOLOGIES LLC

Plugged through: CSG

District: 04

Signed Darrel Dipman (TECHNICIAN) CM
11/8/13

SEP 26 2013

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

OCT 09 2013

CONSERVATION DIVISION
WICHITA, KS