

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-22194-00-00
Spot: NENWSW Sec/Twnshp/Rge: 20-32S-1E
2310 feet from S Section Line, 4290 feet from E Section Line
Lease Name: WEBER Well #: 1-20
County: SUMNER Total Vertical Depth: 4003 feet

Operator License No.: 30129
Op Name: EAGLE CREEK CORPORATION
Address: 150 N MAIN STE 905
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4001		75 SX
SURF	8.625	449		280 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/04/2013 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: DAVID CALLEWAERT Company: EAGLE CREEK Phone: (316) 264-8044

Proposed
Plugging
Method:

SAND TO 3941' & 5 SKS, NO RECOVERY, PERF AT 500' & CIRC CEMENT TO SURFACE.

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 10/04/2013 12:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND BACK TO 3941' & CAPPED WITH 2 SKS CEMENT. NO RECOVERY. PERF'D CASING @ 500', PRESSURED UP, WOULDNT CIRCUALTE. PERF'D AT 450', WELL CIRCUALTED, PUMPED 160 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4001	4003	CSG	

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: CONSOLIDATED CEMENT

Plugged through: CSG

OCT 16 2013

CONSERVATION DIVISION
WICHITA, KS

District: 02

Signed


10/24/13 (TECHNICIAN)

✓ SX