

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-40078-00-00
Spot: NENESENW Sec/Twnshp/Rge: 31-33S-12E
3775 feet from S Section Line, 2867 feet from E Section Line
Lease Name: BRB Well #: 9
County: CHAUTAUQUA Total Vertical Depth: 1018 feet

Operator License No.: 5970
Op Name: ELMORE, JOHN A. OR PATRICIA R.
Address: 776 HWY 99
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	1018		0 SX
SURF	10	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/13/2013 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: JOHN ELMORE Company: _____ Phone: (620) 725-5538

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS WitnessType: NONE
Date/Time Plugging Completed: 05/14/2013 12:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1090 gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 12 sack plug. Pulled up to 350' and circulated cement to surface inside and outside of casing. A total of 142 sacks of cement were used to plug this well.

Perfs:

RECEIVED
SEP 19 2013
KCC Chanute Dist. #3


DS

Remarks:

Plugged through: TBG

District: 03

Signed


6/21/13 (TECHNICIAN)

KCC WICHITA Form CP-2/3

SEP 23 2013

RECEIVED