

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-019-19234-00-00

Spot: SWNWSWNE

Sec/Twnshp/Rge: 31-33S-12E

3547 feet from S Section Line, 2405 feet from E Section Line

Lease Name: RANCH (RIGDON BRUEN FEE Well #: 66

County: CHAUTAUQUA

Total Vertical Depth: 1139 feet

Operator License No.: 5970

Op Name: ELMORE, JOHN A. OR PATRICIA R.

Address: 776 HWY 99

SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	6.25	971		0 SX
SURF	10	20		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/11/2013 12:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ELMORE

Company:

Phone: (620) 725-5538

Proposed Plugging Method: Surface cement and production casing cement unknown. Run 1" to TD. Gel hole. Spot 20 sacks of cement on bottom. Pull out and perforate at 700' and 350'. Run 1" back in and plug with 20 sacks at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS

Witness Type: NONE

Date/Time Plugging Completed: 06/12/2013 12:00 PM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Well had no production casing in it. Washed 1" to 890' gelled hole and spotted 15 sack plug. Pulled up to 550' and spotted 15 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 100 sacks of cement were used to plug this well.

RECEIVED

SEP 19 2013

KCC Chanute Dist. #3

DS

Remarks:

Plugged through: TBG

District: 03

Signed Duane Sims
10/24/13 (TECHNICIAN)

KCC WICHITA Form CP-2/3

SEP 23 2013

RECEIVED