

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-20324-00-00
Spot: NWNWSWSW Sec/Twnshp/Rge: 28-33S-36W
1284 feet from S Section Line, 5193 feet from E Section Line
Lease Name: CARPENTER Well #: 6 SWD
County: STEVENS Total Vertical Depth: 1365 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1365	478	WITH 175 SX CMT
SURF	7	650		WITH 475 SX CMT

Well Type: SWD UIC Docket No: D19002.0 Date/Time to Plug: 07/31/2013 1:00 PM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULLI Phone: (580) 254-1881

Proposed Plugging Method: PUMP 25 SX CMT WITH 100# HULLS ON BOTTOM. PLUG AT 500' WITH 40 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/01/2013 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT & 100# HULLS AT 1200'. 1ST PLUG AT 478' WITH 40 SX CMT. 2ND PLUG AT 90' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1252	1258		

RECEIVED
KANSAS CORPORATION COMMISSION
AUG 23 2013

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED COMMON CEMENT BY SARGENT LILLARD. WICHITA, KS

Plugged through: TBG

District: 01

RECEIVED
AUG 12 2013
KCC DODGE CITY

Signed

[Signature]
8/26/13
(TECHNICIAN)
cc to WME 8/26/13

[Handwritten mark]