

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-067-21518-00-00  
Spot: SESESWNE Sec/Twnshp/Rge: 11-27S-35W  
2317 feet from N Section Line, 1515 feet from E Section Line  
Lease Name: KAUFMAN A Well #: 2  
County: GRANT Total Vertical Depth: 5575 feet

Operator License No.: 5447  
Op Name: OXY USA INC.  
Address: 5 E GREENWAY PLZ PO BOX 27570  
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4507	1912	WITH 260 SX CMT
SURF	8.625	1880		WITH 780 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/15/2013 2:00 PM  
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.  
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 4200' WITH 2 SX CMT OR 25 SX CMT WITH 200# HULLS. PLUG AT 1900' WITH 40 SX CMT. PLUG AT 700' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 10/16/2013 1:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

PUMP 100# HULLS & 25 SX CMT. PRESSURED UP. 1ST PLUG AT 1900' LOADED HOLE WITH MUD THEN SPOTTED 50 SX CMT. 2ND PLUG AT 700' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4242	4246		

KCC WICHITA  
OCT 28 2013  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED  
OCT 19 2013  
KCC DODGE CITY

Signed [Signature]  
10/28/13 (TECHNICIAN)

[Handwritten initials]