

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-047-19004-00-01
Spot: NWSESENE Sec/Twnshp/Rge: 22-24S-16W
3240 feet from S Section Line, 624 feet from E Section Line
Lease Name: SKALSKY Well #: 1
County: EDWARDS Total Vertical Depth: 4584 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3795		
PROD	5.5	4342	0	WITH 175 SX CMT
SURF	8.625	312		WITH 200 SX CMT

Well Type: EOR UIC Docket No: E22097.1 Date/Time to Plug: 08/26/2013 11:00 AM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ADAM APPLEY Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: CIBP @ 3795' FROM PREVIOUS WORK. PERFORATE @ 1100' & CIRCULATE CMT TO SURFACE UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2013 12:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

Perfs:

****SQUEEZED HOLES @ 1906' TO 1968' WITH 685 SX CMT**** CIBP SET @ 3795'.
PERFORATED 5 1/2" @ 1100'. RAN TBG TO 1121'. PUMPED 350 SX CMT. (LOST
CIRCULATION & IT CAME BACK TOWARDS THE END.) WAITED 2 HOURS & RAN
TBG BACK TO 1100'. PUMPED 200 SX CMT CIRCULATING CMT TO SURFACE UP
THE 5 1/2". HAD CIRCULATION UP 8 5/8" X 5 1/2" BUT NO CMT. SDON. 8/27/13:
TAGGED CMT INSIDE 5 1/2" @ 30'. PUMPED 25 SX CMT TOPPING OFF 8 5/8" X 5 1/2"
ANNULUS & THE 5 1/2".

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 04 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

District: 01

RECEIVED
AUG 29 2013
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

cc to WIC 9/04/13
10/21/13