

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-21377-00-00  
Spot: E2SWSWSE Sec/Twnshp/Rge: 11-29S-7W  
330 feet from S Section Line, 2160 feet from E Section Line  
Lease Name: VORAN Well #: 1  
County: KINGMAN Total Vertical Depth: 4210 feet

Operator License No.: 3273  
Op Name: HERMAN L. LOEB, LLC  
Address: PO BOX 838  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4160		150 SX
PROD	4.5	4208		
SURF	8.625	255		
SURF	8.5	275		100 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/17/2013 4:00 PM  
Plug Co. License No.: 32983 Plug Co. Name: STEVE'S WELL SERVICE, INC.  
Proposal Rcvd. from: TRACY BLACK Company: \_\_\_\_\_ Phone: (316) 215-1873

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 09/17/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4050' CAPPED WITH 2 SX CEMENT ON TOP. PERFORATED CASING WITH 4 SHOTS @ 1100' & 650' & 300'. RAN TUBING INTO 1100' SPOTTED 35 SX CEMENT. RAN TUBING INTO 650' SPOTTED 35 SX OF CEMENT. RAN TUBING INTO 300' CIRCULATED TO SURFACE WITH 115 SX CEMENT. WELDED PLATE OVER 8 5/8 CASING.

Perfs:

Remarks: CONSOLIDATED SERVICES OUT OF ELDORADO, PUMPED CEMENT.

Plugged through: TBG

KCC WICHITA  
SEP 24 2013  
RECEIVED

District: 02

Signed

BJ Hope  
10/24/13

(TECHNICIAN)