

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-22650-00-00
Spot: S2SESE Sec/Twnshp/Rge: 22-13S-15W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: OLSON HARMON Well #: 1
County: RUSSELL Total Vertical Depth: 3411 feet

Operator License No.: 34259
Op Name: JAG OPERATIONS, INC.
Address: 710 S. FRONT PO BOX 628
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3304		
PROD	5.5	3411	525	150 SX
SURF	8.625	505		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/26/2013 8:15 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: JACK YOST Company: J A G OIL OPERATION Phone: (785) 445-4142

Proposed Plugging Method: Ordered 250 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Pulled casing out. Put on an overshot, ran back in and over the casing. Ran different mills and bits but only got to 705'.
Could not make any more hole. Top of casing at 525'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/26/2013 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 705' and pumped 200 sx cement.
Cement circulated out braden head and back side.
POOH with tubing and casing 525'.
Pumped 50 sx cement into 8 5/8" casing.
Hole stayed full.

GPS: 38.90104 -098.96753

Perfs:

Top	Bot	Thru	Comments
3199	3202		
2782	2786		

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: QUALITY CEMENTING TICKET # 7296

SEP 09 2013

Plugged through: TBG

CONSERVATION DIVISION
WICHITA, KS

District: 04

Signed Ray A Dinkel
08/26/13 (TECHNICIAN)

CM

AUG 29 2013