

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15318-00-00
Spot: E2SWSE Sec/Twnshp/Rge: 12-17S-11W
660 feet from S Section Line, 1650 feet from E Section Line
Lease Name: KRAFT-PRUSA UT Well #: 6-3
County: BARTON Total Vertical Depth: 3303 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3284		100 SX
SURF	10	274		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2013 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 275-2963

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Perforations: 1300', 620' and 200'

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2013 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2780' and pumped 10 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1350' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 635' and pumped 50 sx cement. Cement circulated. POOH. Hooked up to casing and pumped 145 sx cement at 150 psi. Cement circulated into cellar. Shut in casing.

GPS: 38.58172 -098.48567

Perfs:

Top	Bot	Thru	Comments
3284	3303		

Remarks: ALLIED CEMENTING TICKET # 61941

Plugged through: TBG

District: 04

Signed

Ray A Dinkel
11/14/13

(TECHNICIAN)

CM

OCT 29 2013

KCC WICHITA

Form CP-2/3

NOV 04 2013

RECEIVED