

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-203-20226-00-00
Spot: N2SESWSW Sec/Twnshp/Rge: 3-19S-35W
335 feet from S Section Line, 990 feet from W Section Line
Lease Name: SPLITTER Well #: 1-3
County: WICHITA Total Vertical Depth: 5200 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	347		WITH 225 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/14/2013 5:00 PM
Plug Co. License No.: 5929 Plug Co. Name: DUKE DRILLING CO., INC.
Proposal Rcvd. from: RICH WHEELER Company: DUKE DRILLING CO., INC. Phone: (316) 267-1331

Proposed Plugging Method: 1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 380' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: NONE
Date/Time Plugging Completed: 08/14/2013 5:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

1ST PLUG AT 2400' WITH 50 SX CMT. 2ND PLUG AT 1290' WITH 80 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 380' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY CONSOLIDATED.

Plugged through: DP

RECEIVED
KANSAS CORPORATION COMMISSION

SEP 10 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED

SEP - 6 2013

KCC DODGE CITY

Signed Eric MacLaren
5/5/2013 (TECHNICIAN)

RM