

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21250-00-00
Spot: N2NESENE Sec/Twnshp/Rge: 10-32S-12W
1421 feet from N Section Line, 309 feet from E Section Line
Lease Name: CUNNINGHAM Well #: 1
County: BARBER Total Vertical Depth: 4325 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 4200 | | WITH 2 SX CMT |
| PROD | 4.5 | 4323 | 2400 | WITH 75 SX CMT |
| SURF | 8.625 | 422 | | WITH 275 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/02/2012 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4200' WITH 2 SX CMT. TBG TO 3400'. PUMP 50 SX CMT WITH 100# HULLS WITH COMMON CMT & 3% CC. PLUG AT 600' WITH 600' WITH 10 SX GEL & 100 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2013 10:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF CIBP THRU DUMP BAILER. 1ST PLUG AT 3400' (CSG LEAK) WITH 100# HULLS & 100 SX COMMON CMT WITH 3% CC. 2ND PLUG AT 600' WITH 10 SX GEL & 100 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4248 | 4275 | | |

RECEIVED
KANSAS CORPORATION COMMISSION

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

AUG 19 2013

CONSERVATION DIVISION
WICHITA, KS

District: 01

RECEIVED
AUG - 9 2013
KCC DODGE CITY

Signed

Stephen J Pfeifer

(TECHNICIAN)