

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-24365-00-00
Spot: E2SESWSE Sec/Twnshp/Rge: 18-35S-7E
227 feet from S Section Line, 1472 feet from E Section Line
Lease Name: CHARLES Well #: 1-18
County: COWLEY Total Vertical Depth: 3050 feet

Operator License No.: 34226
Op Name: YALE OIL ASSOCIATION, INC.
Address: 6 NE 63RD ST, STE 425
OKLAHOMA CITY, OK 73105

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3050	998	105 SX
SURF	8.625	301		225 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/04/2013 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Revd. from: JIM MCDANIEL Company: YALE OIL ASSOCIATION Phone: (405) 202-4874

Proposed Plugging Method: AS PER KCC RULES & REGS / CIBP @ 2700 & 2900 W / 2 SXS / PULL PIPE / 355 -0 CIRC CEMENT

Plugging Proposal Received By: DUANE KRUEGER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/04/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

LOADED HOLE W/DRILLING MUD. RIH ON WIRELINE SET CIBP @ 2900'. DUMP BAILED 2 SXS CEMENT ON TOP. RIH ON WIRELINE SET CIBP @ 2700', DUMP BAILED 2 SXS CEMENT ON TOP. LOADED HOLE W/MUD. CUT CASING @ 1200', & 998, LAYED DOWN 25 JTS 5 1/2" CASING (998'). RIH W/TBG @ 372', LOADED HOLE W/MUD, CONSOLIDATED OIL WELL ESTABLISHED CIRCULATION, MIXED & PUMPED 175 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. P & A COMPLETE - 6-4-2013 5:00 PM. CEMENT TICKET #40627.

Perfs:

Top	Bot	Thru	Comments
2969			CSG
2966			CSG
2965			CSG
2959	2969		CSG
2766	2773		CSG

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 2 2 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks:

Plugged through: TBG

District: 02

Signed

Duane Krueger
6/4/13 (TECHNICIAN)