

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-113-21361-00-00
Spot: S2SWSE Sec/Twnshp/Rge: 3-21S-4W
330 feet from S Section Line, 1980 feet from E Section Line
Lease Name: MARY ENTZ TRUST Well #: 1-3
County: MCPHERSON Total Vertical Depth: 1889 feet

Operator License No.: 6804
Op Name: LACHENMAYR OIL LLC
Address: PO BOX 526
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
COND	13.375	97		
SURF	8.625	671		

Well Type: LH UIC Docket No: _____ Date/Time to Plug: 10/15/2013 7:30 PM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/16/2013 5:45 PM KCC Agent: HUNTER CLARK

Actual Plugging Report:

Perfs:

10/15/13 SET 50 SK PLUG @ 728', TAGGED @ 613' KB. 10/16/13 SET 50 SK PLUG @ 408', TAGGED @ 243' KB. BLEW THREW PLUG - SET 50 SK PLUG @ 278', TAGGED @ 247' BLEW THREW PLUG AS WELL NO CIRC. ON THIS PLUG WHILE PUMPING PLUG BROKE LOOSE D.P. WENT ON VACCUM WHEN WE BROKE LOOSE. LOADED HOLE WITH DRILL MUD. SET 30 SK PLUG @ 85', DID NOT TAG THIS PLUG NO CIRC WHILE PUMPING PLUG. DP WENT ON VACCUM AGAIN. RAN PIPE @ 220' PUMPED 1,000 LBS HULLS TOOK 2 MINS TO LOAD HOLE. SET 50 SK PLUG AND 100 LBS HULLS @ 157' GOT CIRC AT END OF PLUG WELL WENT ON VACCUM. TAGGED @ 285' HOLE STAYED FULL OF FLUID. SET 20 SK PLUG @ 241' WITH 50 LBS HULLS TAGGED AT 200' KEPT CIRC. THE COMPLETE TIME OF PUMPING THE PLUG HOLE STAYED FULL OF FLUID. RAN PIPE TO 126' TOOK 30 SKS TO CIRC TO SURFACE. PUMPED 30 SKS IN RAT HOLE, 20 SKS IN MOUSE HOLE. TOPPED WELL OF WITH 10 SKS HOLE STAYED FULL. ALL CEMENT CLASS A COMMON 3% CC. 360 SKS TOTAL AMOUNT.

Remarks: QUALITY WELL SERVICE TICKET #5964 & 5965

Plugged through: DP

KCC WICHITA
OCT 29 2013
RECEIVED

District: 02

Signed: Jeff Klock
10/19/13 (TECHNICIAN)