

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23967-00-00  
Spot: SWSESWNW Sec/Twnshp/Rge: 16-7S-22W  
2851 feet from S Section Line, 4418 feet from E Section Line  
Lease Name: WERTH-WORCESTER NW Well #: 7  
County: GRAHAM Total Vertical Depth: 3930 feet

Operator License No.: 30259  
Op Name: WERTH, ANDY DBA WERTH EXPLORA  
Address: 1308 SCHWALLER AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	218		200 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/10/2013 12:00 AM  
Plug Co. License No.: 33549 Plug Co. Name: LANDMARK DRILLING, LLC  
Proposal Rcvd. from: MAGGIE Company: LANDMARK DRILLING, LLC Phone: (620) 930-2036

Proposed Plugging Method: Ordered 255 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: MARVIN MILLS Witness Type: NONE  
Date/Time Plugging Completed: 10/10/2013 1:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

1st plug @3842 w/50 sx  
2nd plug @1980 w/25 sx  
3rd plug @1170 w/100 sx  
4th plug @270 w/40 sx  
5th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

Remarks: QUALITY  
Plugged through: DP

District: 04

Signed [Signature] (TECHNICIAN) CM

KCC WICHITA

OCT 25 2013

OCT 30 2013

RECEIVED