

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-075-20870-00-00  
Spot: W2E2SEW Sec/Twnshp/Rge: 8-25S-42W  
1980 feet from N Section Line, 2305 feet from W Section Line  
Lease Name: FOX Well #: 3-8  
County: HAMILTON Total Vertical Depth: 1549 feet

Operator License No.: 32283  
Op Name: WESTERN OPERATING COMPANY  
Address: 518 17TH ST STE 200  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	954		WITH 450 SX CMT

Well Type: LH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/29/2013 6:45 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: BERNIE MEYER Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: 1ST PLUG AT 1300' WITH 80 SX CMT. 2ND PLUG AT 60' WITH 20 SX CMT. 3RD PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: NONE  
Date/Time Plugging Completed: 07/29/2013 8:45 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

Perfs:

**\*\*WELL BLEW OUT NIROGEN GAS AT 1342', 1383', & 1549'.\*\*** 1ST PLUG AT 1300' WITH 80 SX COMMON CMT. TAGGED TOC @ 1236'. PUMPED 350 SX CMT. TAGGED TOC @ 653'. 2ND PLUG AT 60' WITH 20 SX CMT. 3RD PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 4TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL 3% CC BY ALLIED.

Plugged through: DP

KCC WICHITA

SEP 17 2013

RECEIVED

District: 01

RECEIVED

AUG - 2 2013

KCC DODGE CITY

Signed

*Michael Maier*  
*M/21/13*

(TECHNICIAN)

*Handwritten mark*