

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22989-00-00
Spot: N2S2SESE Sec/Twnshp/Rge: 24-7S-21W
650 feet from S Section Line, 660 feet from E Section Line
Lease Name: GEIGER GRAIN Well #: 1
County: GRAHAM Total Vertical Depth: 3630 feet

Operator License No.: 34559
Op Name: WM KS ENERGY RESOURCES LLC
Address: 1001 FANNIN, STE 4000
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	1690		
PROD	5.5	3627		170 SX
SURF	8.625	232		160 SX
TI	2.375	3560		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/15/2013 12:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TOM BERENS Company: WMKS ENERGY RES. LLC Phone: (785) 688-4040

Proposed Plugging Method: DV Tool at 1690' w/425 sx cement.
Production flow perforations: 3260' - 3343'
CIBP at 3350'

Ordered 300 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/15/2013 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3325'. Allied pumped 11 sx gel followed by 50 sx cement w/150 # hulls.
Pulled tubing to 1695'. Allied pumped 180 sx cement w/50 # hulls. Cement circulated.
PTOH. Topped 5 1/2" casing off w/15 sx cement. Hooked up to backside and pumped 5 sx
cement. Instant pressure.

Perfs:

Top	Bot	Thru	Comments
3534	3536		

RECEIVED
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED TICKET # 56990

Plugged through: TBG

District: 04

Signed Richard Williams
8/22/13 (TECHNICIAN)

CM

AUG 19 2013