

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-22728-00-00
Spot: SENWSW Sec/Twnshp/Rge: 36-31S-4E
1650 feet from S Section Line, 4290 feet from E Section Line
Lease Name: HOLT Well #: 6
County: COWLEY Total Vertical Depth: 3024 feet

Operator License No.: 34320
Op Name: LASSO ENERGY LLC
Address: PO BOX 465
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2950		
PROD	5.5	3024	413	125 SX
SURF	8.625	216		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/03/2013 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: KURTIS KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 259-4000

Proposed Plugging Method: Per KCC Rules and Regulations.

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 07/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2200', DUMP BAILED 3 SXS CEMENT ON TOP. CUT CASING @ 413', LAYED DOWN 5.5" CASING (413'). RIH W/TBG @ 275', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 112 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7/8/2013.

Perfs:

Top	Bot	Thru	Comments
2929	2937	CSG	

Remarks: COPELAND CEMENT TICKET #42040.

Plugged through: TBG

District: 02

Signed

DUANE KRUEGER
11/26/13 (TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

OCT 22 2013

CONSERVATION DIVISION
WICHITA, KS