

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-30008-00-00  
Spot: SESENW Sec/Twnshp/Rge: 36-31S-4E  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: LOREN HOLT A Well #: 1  
County: COWLEY Total Vertical Depth: 3035 feet

Operator License No.: 34320  
Op Name: LASSO ENERGY LLC  
Address: PO BOX 465  
CHASE, KS 67524

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2275		
PROD	5.5	2423	310	0 SX
SURF	8.625	216		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/02/2013 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: KURTIS KELSO Company: MIKES TESTING & SALVAGE Phone: \_\_\_\_\_

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: B. J. HOPE WitnessType: PARTIAL  
Date/Time Plugging Completed: 07/08/2013 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2275', DUMP BAILED 3 SXS CEMENT ON TOP. CUT CASING @ 310', LAYED DOWN 5.5" CASING, (310'). RIH W/TBG @ 265', COPELAND ACID SERVICE ESTABLISHED CIRCULATION, MIXED & PUMPED 100 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 7/8/2013.

Perfs:

Top	Bot	Thru	Comments
2364	2364	CSG	

RECEIVED  
KANSAS CORPORATION COMMISSION  
OCT 22 2013

Remarks: COPELAND CEMENT TICKET #42039.

Plugged through: TBG

CONSERVATION DIVISION  
WICHITA, KS

District: 02

Signed

DUANE KRUEGER  
M 20/13 (TECHNICIAN)