

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-155-21194-00-00  
Spot: SENEW Sec/Twnshp/Rge: 36-24S-9W  
4011 feet from S Section Line, 2697 feet from E Section Line  
Lease Name: KANATZAR TRUST Well #: 1  
County: RENO Total Vertical Depth: 3970 feet

Operator License No.: 31270  
Op Name: MATTINGLY, INC.  
Address: 729 E CENTRAL  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3691	1796	0 SX
SURF	8.625	260		0 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/11/2013 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 562-8088

Proposed  
Plugging  
Method:

AS PER KCC RULE & REGS

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/11/2013 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND OH TO 3620' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 1796' AND PULL TO 1400' AND PUMP 35 SX'S CEMENT. PULL CASING TO 800' AND PUMP 35 SX'S CEMENT. PULL CASING TO 310' AND CIRCULATE 175 SX'S CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3691	3970	OH	

Remarks: 60-40 POZ, 4 % GEL. COPELAND #41902 TA NOV - DENIED BY BJ HOPE

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
10/16/13  
(TECHNICIAN)

KCC WICHITA  
Form CP-2/3

NOV 04 2013

RECEIVED

✓