

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-077-21565-00-00  
Spot: W2NESWNE Sec/Twnshp/Rge: 11-34S-6W  
1650 feet from N Section Line, 1830 feet from E Section Line  
Lease Name: WIMMER A Well #: 1-11  
County: HARPER Total Vertical Depth: 3900 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E CENTRAL STE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3898	2725	125 SX
SURF	8.625	213		175 SX
T1	2.375	3813		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/01/2013 8:00 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: \_\_\_\_\_ Phone: (316) 636-2737

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/01/2013 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3730' - CAPPED WITH 4 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2725' PULLED CASING TO 950' SPOTTED 35 SX CEMENT. PULLED CASING TO 650' SPOTTED 35 SX CEMENT WITH 3% CC. TAGGED TOC @ 475'. PULLED CASING TO 265' CIRCULATED TO SURFACE WITH 125 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
3804	3809		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT, COMMON CLASS A USED.

Plugged through: CSG

District: 02

Signed

*BJ Hope*

*11/26/13*

(TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 13 2013

RECEIVED

*SK*