

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-19090-00-00
Spot: N2NESW Sec/Twnshp/Rge: 16-14S-14W
2310 feet from S Section Line, 1980 feet from W Section Line
Lease Name: COADY TWIN Well #: 8
County: RUSSELL Total Vertical Depth: 3305 feet

Operator License No.: 8996
Op Name: MID-CONTINENT RESOURCES, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3304		150 SX CEMENT
SURF	8.625	254		150 SX CEMENT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/07/2013 8:30 AM
Plug Co. License No.: 34712 Plug Co. Name: EXPRESS ENERGY SERVICES OPERATING, LP
Proposal Rcvd. from: JOE SMITH Company: MID CONTINENT RESOURCES Phone: (620) 275-2963

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement.
Perforation: 200'.
10/28/2013-Express Well Service moved in and rigged up.
10/29/2013 to 11/04/2013- Ran in and tagged at 455'. Ran wash over pipe, paper mill, taper mill and bit cleaning down to 777'. Every tool ran in well had trouble getting through the 455' spot. 11/04/13- Drilled for 3 hours at 777' not making any hole. Pulled bit and ran in wash over pipe. Hung up at 455'. Pulled out and ran open ended tubing and had trouble at 455' but made it to bottom. Circulated clean cement and pulled out of hole. 11/7/13- ran perforating gun in and could not get down past 462'. Pulled up and shot gun at 200'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/07/2013 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 746' and pumped 130 sx cement. Cement circulated. POOH. Hooked to casing and pumped 45 sx cement. Cement circulated out braden head. Shut in braden head and pressured casing to 400 psi. Shut in.

GPS: 38.83360 -098.88500

Perfs:

Remarks: SWIFT SERVICES TICKET # 25183

Plugged through: TBG

District: 04

Signed

Ray Dinkel
11/26/13

(TECHNICIAN)

KCC WICHITA

CM

NOV 08 2013

NOV 14 2013

Form CP-2/3

RECEIVED