

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24811-00-01
Spot: NESWSEW Sec/Twnshp/Rge: 34-19S-23W
3163 feet from S Section Line, 3391 feet from E Section Line
Lease Name: MONTY Well #: 1-34
County: NESS Total Vertical Depth: 4480 feet

Operator License No.: 5144
Op Name: MULL DRILLING COMPANY, INC.
Address: 1700 N WATERFRONT PKWY BLDG 1200
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
CIBP		4360		
PC		1543		WITH 140 SX CMT
PROD	5.5	4468	0	WITH 135 SX CMT
SURF	8.625	215		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2013 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: KYLE RANDA Company: MULL DRILLING Phone: (785) 798-3306

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. SWAB CASING DOWN TO PORT COLLAR. TIE ONTO CASING & FILL WITH CMT. TIE ONTO BACKSIDE & PUMP 50 SX CMT IF POSSIBLE

Plugging Proposal Received By: MICHAEL MAIER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2013 11:15 AM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT. LOADED HOLE WITH FRESH WATER. SWABBED HOLE DOWN TO 1600'. TIED ONTO CASING & PUMPED 167 SX CMT. PRESSURED TO 500# & HELD. TIED ONTO BACKSIDE & PUMPED 15 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4373	4378		
4292	4300		

Remarks: USED 60/40 POZMIX 4% GEL BY CONSOLIDATED OIL WELL.

Plugged through: CSG

KCC WICHITA

NOV 21 2013

RECEIVED

District: 01

RECEIVED

OCT 29 2013

KCC DODGE CITY

Signed

Michael Maier
10/26/13
(TECHNICIAN)