

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-063-21713-00-02  
Spot: SENESE Sec/Twnshp/Rge: 27-15S-26W  
970 feet from S Section Line, 1380 feet from E Section Line  
Lease Name: THORNBURG TRUST UNIT Well #: 1-27  
County: GOVE Total Vertical Depth: 4475 feet

Operator License No.: 5144  
Op Name: MULL DRILLING COMPANY, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 12  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4375		
PROD	4.5	4471		185 SX
SURF	8.625	224		160 SX
T1	2.375	4343		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/12/2013 10:30 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: KYLE RANDA Company: CONSOLIDATED OIL WELL SERVI Phone: (785) 798-3306

Proposed Plugging Method: Ordered 275 sx 60/40 pozmix 4% gel cement, 300 # hulls and 9 sx gel. CIBP at 4375'. Perforations: 4011' - 4017' and 4402' - 4410'. Port collar at 1932' w/225 sx cement.

Plugging Proposal Received By: MARVIN MILLS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/12/2013 11:00 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Perfs:

Tied on to casing and pumped 50 sx cement w/150 # hulls followed by 9 sx gel, followed by 135 sx cement. Shut in pressure 500 psi. Topped off casing with 2 sx cement. Tied on to backside and pumped 5 sx cement. Shut in pressure 500 psi.


GPS: 38.71495 -100.19534

Remarks: CONSOLIDATED CEMENT TICKET # 44291

Plugged through: CSG

District: 04

Signed

  
11/26/13 (TECHNICIAN)

CM

KCC WICHITA

Form CP-2/3

NOV 25 2013

RECEIVED

NOV 14 2013