

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-23354-00-00  
Spot: NWNE Sec/Twnshp/Rge: 9-7S-21W  
175 feet from N Section Line, 500 feet from E Section Line  
Lease Name: KEN UNIT Well #: 1  
County: GRAHAM Total Vertical Depth: 3798 feet

Operator License No.: 34559  
Op Name: WM KS ENERGY RESOURCES LLC  
Address: 1001 FANNIN, STE 4000  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3797		165 SX
SURF	8.625	212		160 SX
TI	2.875	3575		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/09/2013 8:30 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: BILL ROBINSON Company: WMKS ENERGY RES. LLC. Phone: (785) 688-4040

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 13 sx gel and 200 # hulls.  
Production perforations: 3590' - 3602'  
DV Tool at 1764' w/240 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/09/2013 12:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3564' and pumped 13 sx gel followed by 50 sx cement w/200 # hulls.  
Pulled tubing to 1816' and pumped 200 sx cement to circulate cement to surface.  
Pulled tubing and topped off 5 1/2" casing with 25 sx cement.  
Hooked to 8 5/8"x5 1/2" annulus and pressured to 300 psi immediately.

GPS: 39.46609N -099.65964W

Perfs:

Top	Bot	Thru	Comments
3600	3602		
3590	3602		

RECEIVED  
KANSAS CORPORATION COMMISSION

AUG 23 2013

CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING TICKET # 54722

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

*Pat Bedore*  
(TECHNICIAN)

CM

Form CP-2/3

AUG 19 2013