

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23118-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 12-9S-22W
1130 feet from N Section Line, 1965 feet from W Section Line
Lease Name: BUSS B Well #: 2
County: GRAHAM Total Vertical Depth: 3893 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3892		445 SX
SURF	8.625	212		150 SX
T1	2.875	3867		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/25/2013 8:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. Phone: (785) 483-8355

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement, 15 sx gel and 400 # hulls.
5 1/2" casing cemented bottom to surface.
Production perforations: 3800' - 3820'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2013 12:30 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Ran tubing to 3800'. Quality Oil Well Cementing pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1750'. Quality pumped 175 sx cement w/200 # hulls. Cement circulated. PTOH. Topped 5 1/2" casing w/25 sx cement. Casing full. Hooked up to backside. Instant pressure at 300 psi.

Perfs:

Top	Bot	Thru	Comments
3800	3820		

Remarks: QUALITY

Plugged through: TBG

District: 04

Signed R. Williams (TECHNICIAN) 10/19/13 CM

OCT 29 2013

KCC WICHITA Form CP-2/3

NOV 04 2013

RECEIVED