

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21730-00-00
Spot: SWSESWNW Sec/Twnshp/Rge: 17-12S-17W
2932 feet from S Section Line, 4397 feet from E Section Line
Lease Name: SCHMEIDLER A Well #: 13
County: ELLIS Total Vertical Depth: 3716 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3702		150 SX
SURF	8.625	251		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/08/2013 10:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: JEFF Company: PROFESSIONAL PULLING Phone: (785) 623-3876

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 9 sx gel and 400 # hulls.
Anh- 1380' - 1412'. Perforated at 1330' and circulated cement to surface w/ 237 sx cement.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE
Date/Time Plugging Completed: 11/08/2013 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3600' and pumped 9 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1800' and pumped 125 sx cement w/300 # hulls to circulate cement to surface. Topped off w/20 sx cement. Tied on to back side and pumped 5 sx cement. 300 psi shut in.

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: TBG

District: 04

Signed CASE MORRIS
11/19/13 (TECHNICIAN)

KCC WICHITA

Form CP-2/3

NOV 08 2013

NOV 14 2013

RECEIVED