

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-03311-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 16-15S-13W
4785 feet from S Section Line, 1155 feet from E Section Line
Lease Name: SCHULTZ Well #: 3
County: RUSSELL Total Vertical Depth: 3070 feet

Operator License No.: 7383
Op Name: GRADY BOLDING CORPORATION
Address: PO BOX 486
ELLINWOOD, KS 67526

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD | 5.5 | 3050 | | 150 SX |
| SURF | 8.625 | 43 | | 50 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/18/2013 7:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORP Phone: (620) 564-2240

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 14 sx gel and 600 # hulls.
Perforations: 1450', 850', 500' and 100'

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/18/2013 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 2900' and pumped 14 sx gel followed by 75 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 870' and pumped 165 sx cement. Cement circulated out the backside. POOH. Hooked up to casing and pumped 110 sx cement. Cement circulated out the braden head. Shut in casing w/200 psi.

GPS: 38.752274 -098.76975

Remarks: COPELAND ACID AND CEMENTING TICKET # 41909

Plugged through: TBG

District: 04

Signed

Ray Dinkel
10/19/13 (TECHNICIAN)

CM

OCT 22 2013

KCC WICHITA

Form CP-2/3

OCT 29 2013

RECEIVED