

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-08577-00-00  
Spot: NE Sec/Twnshp/Rge: 16-15S-13W  
2970 feet from S Section Line, 1980 feet from E Section Line  
Lease Name: SCHULTZ Well #: 5  
County: RUSSELL Total Vertical Depth: 3335 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3324		150 SX
SURF	8.625	150		125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/17/2013 8:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORP. Phone: (620) 564-2240

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 600 # hulls and 10 sx gel. Perforations: 1450', 850', 500' and 150'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/17/2013 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Ran tubing to 3008' and pumped 10 sx gel followed by 50 sx cement w/50 # hulls. Pulled tubing to 1500' and pumped 175 sx cement. Cement circulated out the backside. Shut in and pumped 20 sx cement w/little return out braden head. POOH. Hooked up to casing and pumped 60 sx cement. Cement circulated out braden head into cellar. Shut in casing.

GPS: 38.74857 -098.76980

Remarks: COPELAND ACID AND CEMENTING TICKET # 41918

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*  
*10/19/13*

(TECHNICIAN)

CM

KCC WICHITA

OCT 24 2013

RECEIVED

Form CP-2/3

OCT 21 2013