

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25666-00-00
Spot: SWSNWSW Sec/Twnshp/Rge: 16-17S-22W
1585 feet from S Section Line, 947 feet from W Section Line
Lease Name: MCCURDY Well #: 1
County: NESS Total Vertical Depth: 4400 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
DVT		1574		WITH 350 SX CMT
PLG	5.5	4365		
PROD	5.5	4399	0	WITH 500 SX CMT
SURF	8.625	217		WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/24/2013 2:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: JOHN LOWRY Company: HESS OIL COMPANY Phone: (620) 241-4640

Proposed Plugging Method: RUN TBG TO 4300' & PUMP 18 SX GEL & 35 SX CMT. PULL TBG TO 1590' & CIRCULATE CMT TO SURFACE. PULL TBG & TOP OFF HOLE. PRESSURE 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 10/24/2013 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

RAN TBG TO 4315'. PUMPED 18 SX GEL & 50 SX CMT. PULLED TBG TO 1560' & CIRCULATED CMT TO SURFACE UP THE 5 1/2" CASING WITH 175 SX CMT. PULLED TBG OUT & TOPPED OFF 5 1/2" CASING WITH 5 SX CMT. PRESSURED 8 5/8" X 5 1/2" ANNULUS TO 500 PSIG WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4328	4338		

Remarks: USED 60/40 POZMIX 45 GEL BY SWIFT CEMENTING.

Plugged through: TBG

KCC WICHITA

OCT 29 2013

RECEIVED

District: 01

RECEIVED

OCT 25 2013

KCC DODGE CITY

Signed

Richard M. Lacey
10/19/13 (TECHNICIAN)