

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21124-00-00  
Spot: NWNEENE Sec/Twnshp/Rge: 4-12S-22W  
4985 feet from S Section Line, 648 feet from E Section Line  
Lease Name: SMITH GUY Well #: 1  
County: TREGO Total Vertical Depth: 4140 feet

Operator License No.: 3194  
Op Name: TRI UNITED, INC  
Address: 950 270TH AVE  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4075		
PROD	4.5	4140		150 SX
SURF	8.625	265		155 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/23/2013 2:30 PM  
Plug Co. License No.: 3194 Plug Co. Name: TRI UNITED, INC  
Proposal Rcvd. from: EUGENE LEIKER Company: TRI UNITED, INC Phone: (785) 628-3670

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement and 500 # hulls.  
Perforations at 4003' - 4018'.  
Shot perforations at 2450', 1850', 1000' and 260'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/23/2013 5:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3900' and pumped 150 sx cement w/200 # hulls. Pulled tubing to 2450' and pumped 125 sx cement w/100 # hulls. Pulled tubing to 1000' and pumped 120 sx cement. Casing full. Backside full. Topped off casing w/25 sx cement. Hole standing full.  
GPS: 39.04402 -099.76260

Perfs:

Top	Bot	Thru	Comments
4003	4018		

Remarks: SOS CEMENTING TICKET # 1137

Plugged through: TBG

District: 04

Signed Marvin Mills  
(TECHNICIAN) CM  
11/27/13  
KCC WICHITA

NOV 04 2013

RECEIVED