

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-20471-00-00  
Spot: SESESESE Sec/Twnshp/Rge: 15-10S-19W  
150 feet from S Section Line, 150 feet from E Section Line  
Lease Name: NUTSCH A Well #: 1  
County: ROOKS Total Vertical Depth: 1200 feet

Operator License No.: 3444  
Op Name: KARLIN, GENE DBA GENE KARLIN CO  
Address: 1111 OAKMONT ST  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	1200		200 SX

Well Type: SWD UIC Docket No: D16837.0 Date/Time to Plug: 10/14/2013 12:00 AM  
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING  
Proposal Rcvd. from: GENE KARLIN Company: GENE KARLIN CO. Phone: (785) 483-2025

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/600 # hulls.  
Dug out casing. No surface pipe. Found 2 1/2" tubing cemented inside of 5 1/2" casing to surface.  
Perforations: 996' - 1155'.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 10/14/2013 1:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Quality Oilwell Cementing pumped 15 bbl water 2 1/2" bpm at 200 psi. Followed with 70 sx cement w/300 # hulls. Maximum pressure 800 psi. Shut in pressure 400 psi.

Perfs:

Top	Bot	Thru	Comments
1141	1155		
1086	1106		
1060	1072		
1030	1038		
1022	1026		
1012	1016		
1004	1008		
996	1000		

Remarks: QUALITY OILWELL

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

cc to WIC 11/2/13  
M 10/13

RECEIVED  
KANSAS CORPORATION COMMISSION

CM

Form CP-2/3

OCT 15 2013

OCT 23 2013

CONSERVATION DIVISION  
WICHITA, KS