

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23434-00-00
Spot: E2SWSWSW Sec/Twnshp/Rge: 29-33S-11W
328 feet from S Section Line, 542 feet from W Section Line
Lease Name: HARBAUGH Well #: 1-29
County: BARBER Total Vertical Depth: 4950 feet

Operator License No.: 5039
Op Name: AGV CORP.
Address: PO BOX 377
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4700		
L1	4.5	3980		WITH 175 SX CMT
PROD	5.5	4914	0	WITH 260 SX CMT
SURF	8.625	595		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/13/2013 9:00 AM
Plug Co. License No.: 34227 Plug Co. Name: AMERICAN WELL SERVICE LLC
Proposal Rcvd. from: KENT ROBERTS Company: AGV CORP Phone: (620) 254-7222

Proposed Plugging Method: PUMP DOWN 4 1/2" LINER WITH 200# HULLS & 75 SX COMMON CMT WITH 3% CC. PERFORATE THROUGH 4 1/2" LINER & 5 1/2" AT 620'. PUMP DOWN 4 1/2" LINER & CIRCULATE CMT TO SURFACE UP 5 1/2" X 8 5/8" ANNULUS.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2013 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

FOUND THAT 5 1/2" CASING HAD BEEN BULL HEAD SQUEEZED WITH 100 SX CMT. PUMPED DOWN 4 1/2" LINER WITH 400# HULLS & 75 SX CMT FOLLOWED BY 25 SX (52 BBLs) OF GEL & 50 SX CMT. SHUT DOWN. WELL ON SLIGHT VACUUM. LET CMT SET. VISUALLY CHECKED BACK SIDE OF 4 1/2" LINER & BACK SIDE OF 5 1/2" PRODUCTION CASING & FOUND BOTH STANDING FULL @ SURFACE WITH CMT. PUMPED BACK DOWN 4 1/2" WITH 24 SX CMT. PRESSURED TO 500#. CMT AT SURFACE.

Perfs:

Top	Bot	Thru	Comments
4788	4800		
4550	4564		
4514	4536		


Remarks: USED COMMON CMT WITH 3% CC BY ALLIED.

Plugged through: CSG

District: 01

RECEIVED
NOV 20 2013
KCC DODGE CITY

Signed


(TECHNICIAN)

KCC WICHITA

NOV 25 2013

RECEIVED

Form CP-2/3

