

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-055-21780-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 27-23S-32W
1250 feet from N Section Line, 1250 feet from E Section Line
Lease Name: BOYD Well #: 1-27
County: FINNEY Total Vertical Depth: 2850 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 3 SX CMT
PROD	5.5	2850	0	WITH 350 SX CMT
SURF	8.625	460		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/18/2013 8:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Revd. from: JOSE Company: AMERICAN WARRIOR Phone: (620) 275-2963

Proposed Plugging Method: CIBP @ 2600' WITH 3 SX CMT. PLUG AT 2000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 1000' WITH 50 SX CMT. PLUG AT 490' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/18/2013 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2600' WITH 3 SX CMT. 1ST PLUG AT 2007' WITH 50 SX CMT. 2ND PLUG AT 1010' WITH 50 SX CMT. 3RD PLUG AT 475' WITH 50 SX CMT. 4TH PLUG AT 30' WITH 20 SX CMT. RAN 1" DOWN 5 1/2" X 8 5/8" ANNULUS & TAGGED TOC @ 50'. FULL OF FLUID TO SURFACE. CIRCULATE ANNULUS FULL OF CMT FROM 40' TO 0' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2648	2722		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

KCC WICHITA

NOV 21 2013

RECEIVED


District: 01

RECEIVED

NOV 19 2013

KCC DODGE CITY

Signed



(TECHNICIAN)