

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20258-00-00
Spot: SENWNE Sec/Twnshp/Rge: 19-31S-21W
4727 feet from S Section Line, 663 feet from E Section Line
Lease Name: SEACAT Well #: 5-19
County: CLARK Total Vertical Depth: 5428 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5180		WITH 2 SX CMT
PROD	5.5	5427	1170	WITH 100 SX CMT
SURF	8.625	610		WITH 450 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/18/2013 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: CIBP @ 5180' WITH 2 SX CMT. LOAD HOLE WITH MUD. PLUG AT 1150' WITH 50 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: PARTIAL
Date/Time Plugging Completed: 11/18/2013 2:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 5180' WITH 2 SX CMT. 1ST PLUG CIRCULATED HOLE WITH MUD AT 1150' & PUMPED 50 SX CMT. 2ND PLUG AT 630' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2	5234		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR SENT** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed: Nathan Willis
11/26/13 (TECHNICIAN)

RECEIVED
NOV 20 2013
KCC DODGE CITY

KCC WICHITA Form CP-2/3
NOV 25 2013
RECEIVED