

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-30085-00-00
Spot: NENESWSW Sec/Twnshp/Rge: 9-34S-43W
1270 feet from S Section Line, 3987 feet from E Section Line
Lease Name: INTERSTATE D Well #: 3-9
County: MORTON Total Vertical Depth: 1358 feet

Operator License No.: 7300
Op Name: BEARTOOTH OIL & GAS COMPANY
Address: PO BOX 2564
BILLINGS, MT 59103

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	7	1303	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/19/2013 9:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Revd. from: KEN CURREY Company: BEARTOOTH OIL & GAS Phone: (970) 858-4158

Proposed Plugging Method: Pump a bottom plug that fills 55' of openhole and extend up into at least the bottom 50' of casing. Then pump an upper plug from 350' to surface.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2013 1:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

TBG PARTED @ 1260'. PUMP 48 SX CMT WITH 200# HULLS ON BOTTOM. LET SET FOR 2 HOURS. TAGGED TOC @ 843'. PUMPED A 16 BBL MUD SPACER TO 400'. PUMPED CMT TO SURFACE WITH 77 SX CMT. SHUT IN AT 500#.

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

Signed Eric MacLaren
11/20/13 (TECHNICIAN)

RECEIVED
NOV 20 2013
KCC DODGE CITY

KCC WICHITA Form CP-2/3
NOV 25 2013
RECEIVED