

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-175-20448-00-00  
Spot: SESWNWSW Sec/Twnshp/Rge: 9-32S-31W  
1391 feet from S Section Line, 4669 feet from E Section Line  
Lease Name: BECK Well #: 1-9  
County: SEWARD Total Vertical Depth: 6015 feet

Operator License No.: 31021  
Op Name: CASTELLI EXPLORATION, INC.  
Address: 6908 W 112TH  
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5460		WITH 2 SX CMT
CIBP		5850		
PROD	5.5	6015	1573	WITH 200 SX CMT
SURF	8.625	1510		WITH 880 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/19/2013 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5460' WITH 2 SX CMT. PLUG AT 1540' WITH 20 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/19/2013 1:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 5460' WITH 2 SX CMT. 1ST PLUG AT 1545' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 567' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT. GOOD RETURNS.

Perfs:

Top	Bot	Thru	Comments
5880	5886		
5564	5570		
5517	5520		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED  
NOV 20 2013  
KCC DODGE CITY

Signed Nathan Willis  
11/26/13 (TECHNICIAN)

KCC WICHITA  
NOV 25 2013  
RECEIVED