

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-057-20563-00-00
Spot: S2NWNWNE Sec/Twnshp/Rge: 14-28S-21W
4820 feet from S Section Line, 2310 feet from E Section Line
Lease Name: VICE Well #: 1-14X
County: FORD Total Vertical Depth: 5150 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4250		WITH 2 SX CMT
COND	13.375	150		
PROD	4.5	5136	2188	WITH 230 SX CMT
SURF	8.625	683		WITH 250 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/15/2013 12:30 PM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Revd. from: BUD NEFF Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 4250' WITH 2 SX CMT. PLUG AT 1380' WITH 15 SX GEL & 50 SX CMT. PLUG AT 710' WITH 50 SX CMT. PLUG AT 430' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2013 3:20 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4250' WITH 2 SX CMT. 1ST PLUG AT 1365' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 718' WITH 50 SX CMT. 3RD PLUG AT 437' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT CIRCULATED & HOLE STAYED FULL.

Perfs:

Top	Bot	Thru	Comments
4313	4317		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

NOV 20 2013

KCC DODGE CITY

Signed

Eric MacLaren
11/26/13

(TECHNICIAN)

KCC WICHITA

NOV 25 2013

RECEIVED

Form CP-2/3